HM ROYAL
SOLUTIONS Ltd

Makongo Secondary School Office No 21/22 Near Mwenge, Bagamoyo Road,

P.O. Box 66730, Dar-es-Salaam, Tanzania. Tel ; 0787-289-182/ 0682-201-072

PROFORMA INVOICE

CLIENT'S NAME: SINCRO HQ **Proforma invoice no:**

CLIENT'S ADDRESS: MIKOCHENI **Customer no:0654491973**

DATE: 30/07/2022 **Email : joaqim@sincrositewatch.com**

Project name – Renovation of the Office Building

S/N	DESCRIPTIONS	UNIT	QUANTITY	UNIT PRICE	TOTAL
Roof Repair at Main Building Summit; Involve an identifying of the root cause of leaking, removing of the existing plastered summit floor surface to concrete, put new motor of 6cm mixed with waterproof material and fine aggregates. Then paint a waterproof painting to protect the leaking.					
1	Cement	Bags	40	15,500	620,000
2	Fine aggregates	M3	**8**	110,000	880,000
3	Sand	M3	**16**	30,000	480,000
4	Water proofing	Kg	**80**	4,000	320,000
5	PVC Pipe 2 inches	Pcs	8	25,000	200,000
6	Elbow	Pcs	15	6,000	90,000
7	T connector	Pcs	6	6,000	36,000
8	High cover water proofing solution	Bkt	2	350,000	700,000
				Material subtotal	**3,326,000**
Main building and two store buildings renovation; Consist of removing some plastered surface in the walls both interior and exterior, repairs of the cracked walls replacing with new plasters mixed with water proofing material for controlling of moisture and ceiling replacement at one most affected room. Channeling the tapped and collected water with the right channeling to destinations.					
1	Sand	M3	10	30,000	300,000
2	Cement	Bags	10	15,500	155,000
3	Water proofing material	Kg	15	4,000	60,000
4	Gypsum board	Pcs	10	18,000	180,000
5	Steel ceiling solutions	Set			250,000
6	Screw	Box	2	12,000	24,000

HM ROYAL SOLUTIONS LTD

HM ROYAL
SOLUTIONS Ltd

				Material subtotal	**969,000**
Fence treatment; Removing of old plastered surface and replacing with a new one with water proofing materials. Treating the drainage system and real surface floor with new plastered material.					
6	Cement	Bags	**25**	15,500	387,500
7	Sand	M3	**10**	30,000	300,000
8	Water proofing	Kg	**60**	4000	240,000
				Material subtotal	927,500
Painting; Main building interior door and grill paintings. Apply skimming material and under coat primer, then after the top coat of acrylic paint on walls. Applying undercoat and top coat at the concrete sealing.					
1	Wallputty	Bags	**15**	25,000	400,000
2	Binder	Bkt	**2**	90,000	180,000
3	Sanding	Rolers	**1**	70,000	70,000
4	Silk interior paint	Bkt	**4**	150,000	600,000
5	Strong guard	Bkt	**2**	120,000	240,000
6	Sanding sealer	Tin	**3**	55,000	165,000
7	Oil paint	Tin	**10**	25,000	250,000
8	Thinner	Gln	**4**	28,000	112,000
9	Sanding	Roler	**2**	70,000	140,000
				Material subtotal	**2,157,000**
Painting; Exterior Main building and the two stores and the Fence. Repair of the main entrance gate by removing the rusted material and paint, applying anti rusting undercoat paint and final oil paint top coat.					
8	Wallputty	Bags	**15**	25,000	375,000
8	Binder	Bkt	**2**	90,000	180,000
	Sanding	Rolers	**2**	70,000	140,000
7	Weather guard	Bkt	**4**	150,000	600,000
8	Red ofxide primer	Tin	**2**	30,000	60,000
8	Anti-rusting paint	Tin	**2**	55,000	110,000
				Material subtotal	1,465,000
				Total material	**8,844,500**
				Labour Charge	**5,000,000**

HM ROYAL SOLUTIONS LTD

HM ROYAL
SOLUTIONS Ltd

Total	**13,844,500**


Payment:

Our Bank Details:

Bank Name: NMB

Account Name: HM ROYAL SOLUTION LIMITED

Account No: 23510040716

Director Name: **Haig Mtebe** **Signature:** 

Client Name: **Signature:**

WE THANK YOU FOR WORKING WITH US

HM ROYAL SOLUTIONS LTD